

Jericho Wind, LP

Project Modification Report – Jericho Wind Energy Centre



Environment

tel

fax



Jericho Wind, LP

## Project Modification Report – Jericho Wind Energy Centre

Prepared by:AECOM105 Commerce Valley Drive West, Floor 7905 886 7022Markham, ON, Canada L3T 7W3905 886 9494www.aecom.com

Project Number: 60301207

Date: July, 2014



page

# **Table of Contents**

1.	Intro	oduction	3
	1.1	The Proponent	
	1.2	Project Study Area	3
2.	Prop	bosed Project Modification	4
3.	Edits	s to the initial REA Reports	6
4.	Sum	imary and Conclusions	11

### **List of Figures**

Figure 2-1	Project Location	5
------------	------------------	---

### **List of Tables**

Table 3-1 Edits to the Initial REA Reports	Table 3-1	Edits to the Initial REA Reports
--	-----------	----------------------------------

### Appendices

Appendix A. Hydrogeological Report in Support of a Modification to the Renewable Energy Approval for the Jericho Wind Energy Centre

### **Glossary of Terms**

Jericho	.Jericho Wind, LP
NextEra	.NextEra Energy Canada, LP
REA	.Renewable Energy Approval
The Project	.Jericho Wind Energy Centre

# 1. Introduction

Jericho Wind, LP (Jericho) is constructing a wind energy project in the Municipality of Lambton Shores and the Township of Warwick, in Lambton County, Ontario and in the Municipality of North Middlesex, in Middlesex County, Ontario. The following sections of this Renewable Energy Approval (REA) Project Modification Report describe the proposed modification to this Project and resulting updates to the Construction Plan Report and Project Description Report.

### 1.1 The Proponent

The Project will be owned and operated by Jericho, a wholly owned subsidiary of NextEra Energy Canada, LP (NextEra). NextEra's indirect parent company is NextEra Energy Resources, LLC. Please note that the REA was reassigned from Jericho Wind, Inc. to Jericho Wind, LP on June 11, 2014 and notice of the change was provided to the Ministry of Environment (MOE) on June 25, 2014.

The primary contacts for the Project are as follows:

Project Proponent	Project Consultant
Ben Greenhouse Director, Development NextEra Energy Canada, LP 390 Bay Street, Suite 1720 Toronto, ON M5H 2Y2	Marc Rose Senior Environmental Planner AECOM 105 Commerce Valley Drive West, Floor 7 Markham, ON, Canada L3T 7W3
Phone:1-905-335-4904 Email:Jericho.Wind@NextEraEnergy.com Website:www.NextEraEnergyCanada.com	Phone:1-905-747-7793 Email:marc.rose@aecom.com

### 1.2 Project Study Area

The proposed Project is located in the Municipality of Lambton Shores and the Township of Warwick, in Lambton County, Ontario and in the Municipality of North Middlesex, in Middlesex County, Ontario (refer to **Figure 2-1**). The Project Study Area has not changed from the initial REA submission.

The following co-ordinates define the external boundaries of the Project Study Area:

### **UTM Coordinates**

Easting	Northing
420938	4761752
419681	4780912
456597	4777307
453312	4766484



# 2. Proposed Project Modification


Jericho is proposing to increase the construction dewatering allowance, as outlined in Condition H2 of the REA issued on April 14, 2014, during the excavation and installation of turbine foundations.

The extraction of groundwater for construction dewatering purposes is expected to be of low volume due to the short duration of dewatering activities, and the shallow depth of the turbine bases (up to 4 metres below ground surface). However, there is the potential for water taking above 400,000 L/day to be required depending on the surficial material being excavated, the depth to groundwater, the amount of precipitation received during excavation activities, and other geological characteristics that were observed during the geotechnical investigation.

Based on the analysis of the geotechnical study prepared by AMEC (2013), available geological mapping, MOE water well record borehole logs, and potential precipitation during excavation, Jericho has determined that all turbines proposed for the Project, excluding turbines that have already been constructed, have the potential to require construction dewatering of groundwater greater than 400,000 L/day and surface water up to 1,000,000 L/day during the excavation and installation of turbine foundations. As such the water taking may be classified as Groundwater – Category 3 (taking greater than 400,000 L/day). In all cases, Jericho will only remove the minimum amount of water needed for safe construction practices.

A Hydrogeological Report has been included in **Appendix A** in support of this modification. The report provides background information on the proposed undertaking, the physical setting of the site, and rationale for the change in dewatering requirements. The report also provides a list of the turbines with the potential to require water taking above 400,000 L/day, and the following details about each turbine:

- 1. The subsurface hydrogeological conditions and estimated zone of influence from water taking activities; and,
- 2. New potential environmental effects from groundwater drawdown in nearby features and corresponding mitigation measures.





# 3. Edits to the initial REA Reports

**Table 3-1** documents the edits to the initial REA Reports and associated Revision Reports resulting from the modifications described in **Section 2**. The table includes the text from the original REA submission (February, 2013) and the REA revision reports (October, 2013), and edits to the text (underlined text represents additions and strikethrough text represents deletions).



#### Table 3-1 Edits to the Initial REA Reports

Revised Text Section / Page in REA Combined REA Report and Revision Report text Report (Underlined text represents additions and strikethrough text represents deletions.) **Project Description Report** Table 3-2 / page 26 Mitigation Strategy Mitigation Strategy • Limit dewatering where turbines are constructed within the sand and/or gravel deposits to less than 400,000 L/day. • Limit dewatering where turbines are constructed within the sand and/or gravel deposits to less than 400,000 L/day. Table 3-2 / page 25-26 Monitoring Plan and Contingency Measures Monitoring Plan and Contingency Measures • For significant natural features within the zone of influence and potentially affected by dewatering activities, the following Monitoring Plan • For significant natural features within the zone of influence and potentially affected by dewatering activities, the following Monitoring Plan will will be implemented: be implemented: Prior to construction, undertake monthly monitoring for a minimum of six months of surface water levels (staff gauge), stream Prior to construction, undertake monthly monitoring for a minimum of six months of surface water levels (staff gauge), stream flow (if applicable), vertical hydraulic gradients (mini-piezometers), surface water temperature and vegetation health of the feature flow (if applicable), vertical hydraulic gradients (mini-piezometers), surface water temperature and vegetation health of the feature within the identified dewatering zone of influence. within the identified dewatering zone of influence. - During construction dewatering activities, undertake daily monitoring of surface water levels (staff gauge), stream flow (if - During construction dewatering activities, undertake daily monitoring of surface water levels (staff gauge), stream flow (if applicable), vertical hydraulic gradients (mini-piezometers), surface water temperature and vegetation health of the feature within applicable), vertical hydraulic gradients (mini-piezometers), surface water temperature and vegetation health of the feature within the identified dewatering zone of influence the identified dewatering zone of influence. Following construction, undertake monthly monitoring for up to one year of surface water levels (staff gauge), stream flow (if Following construction, undertake monthly monitoring for up to one year of surface water levels (staff gauge), stream flow (if applicable), vertical hydraulic gradients (mini-piezometers), surface water temperature, and vegetation health of the feature within applicable), vertical hydraulic gradients (mini-piezometers), surface water temperature, and vegetation health of the feature within the identified dewatering zone of influence. Monitoring may be terminated prior to one year postconstruction if there is no evidence the identified dewatering zone of influence. Monitoring may be terminated prior to one year postconstruction if there is no evidence of residual effects and levels have returned to norms established through pre-construction monitoring. of residual effects and levels have returned to norms established through pre-construction monitoring. Prior to construction, conduct site reconnaissance visit and record surface water level (if present) prior to construction dewatering. During Construction, If surface water is present prior to dewatering, monitor surface water levels daily during construction dewatering. Following construction, undertake monthly monitoring for up to one year of surface water levels of the feature within the identified dewatering zone of influence if a decline is recorded during construction dewatering and the decline is a result of dewatering activities. Monitoring may be terminated prior to one year post-construction if initial monitoring determines that there is no evidence of residual effects and levels have returned to pre-construction condition. Contingency Measures: Contingency Measures: In the event of a decrease in surface water levels which can be attributed to the dewatering activities, stop dewatering until In the event of a decrease in surface water levels which can be attributed to the dewatering activities, stop dewatering until appropriate site-specific mitigation has been implemented. Implement contingency measures (to be determined in consultation with appropriate site-specific mitigation has been implemented. Implement contingency measures (to be determined in consultation with MNR), if required, including but not limited to rescue of stranded wildlife MNR), if required, including but not limited to rescue of stranded wildlife. Implement contingency measures, if required, including but not limited to rescue of stranded wildlife and/or directing dewatering discharge towards the feature after applying appropriate water quality and temperature controls. Mitigation Strategy Table 3-3 / page 34 Mitigation Strategy Limit dewatering where turbines are constructed within the sand and/or gravel deposits to less than 400,000 L/day. • Limit dewatering where turbines are constructed within the sand and/or gravel deposits to less than 400,000 L/day. Table 3-3 / page 33-34 Monitoring Plan and Contingency Measures Monitoring Plan and Contingency Measures • For significant natural features within the zone of influence and potentially affected by dewatering activities, the following Monitoring Plan • For significant natural features Turtle Wintering Habitat within the zone of influence and potentially affected by dewatering activities, the following Monitoring Plan will be implemented: will be implemented. Prior to construction, undertake monthly monitoring for a minimum of six months of surface water levels (staff gauge), stream Prior to construction, undertake monthly monitoring for a minimum of six months of surface water levels (staff gauge), stream flow (if applicable), vertical hydraulic gradients (mini-piezometers), surface water temperature and vegetation health of the feature flow (if applicable), vertical hydraulic gradients (mini-piezometers), surface water temperature and vegetation health of the feature within the identified dewatering zone of influence. within the identified dewatering zone of influence. - During construction dewatering activities, undertake daily monitoring of surface water levels (staff gauge), stream flow (if During construction dewatering activities, undertake daily monitoring of surface water levels (staff gauge), stream flow (if applicable), vertical hydraulic gradients (mini-piezometers), surface water temperature and vegetation health of the feature within applicable), vertical hydraulic gradients (mini-piezometers), surface water temperature and vegetation health of the feature within the identified dewatering zone of influence. the identified dewatering zone of influence. Following construction, undertake monthly monitoring for up to one year of surface water levels (staff gauge), stream flow (if Following construction, undertake monthly monitoring for up to one year of surface water levels (staff gauge), stream flow (if applicable), vertical hydraulic gradients (mini-piezometers), surface water temperature, and vegetation health of the feature within applicable), vertical hydraulic gradients (mini-piezometers), surface water temperature, and vegetation health of the feature within the identified dewatering zone of influence. Monitoring may be terminated prior to one year postconstruction if there is no evidence the identified dewatering zone of influence. Monitoring may be terminated prior to one year postconstruction if there is no evidence of residual effects and levels have returned to norms established through pre-construction monitoring. of residual effects and levels have returned to norms established through pre-construction monitoring. Contingency Measures: Contingency Measures: In the event of a decrease in surface water levels which can be attributed to the dewatering activities, stop dewatering until In the event of a decrease in surface water levels which can be attributed to the dewatering activities, stop dewatering until appropriate site-specific mitigation has been implemented. Implement contingency measures (to be determined in consultation with appropriate site-specific mitigation has been implemented. Implement contingency measures (to be determined in consultation with MNR), if required, including but not limited to rescue of stranded wildlife. MNR), if required, including but not limited to rescue of stranded wildlife • For Significant Wetlands and Amphibian Woodland Breeding Habitat within the zone of influence and potentially affected by dewatering activities, the following Monitoring Plan will be implemented: Prior to construction, conduct site reconnaissance visit and record surface water level (if present) prior to construction dewatering. During Construction, If surface water is present prior to dewatering, monitor surface water levels daily during construction dewatering. Following construction, undertake monthly monitoring for up to one year of surface water levels of the feature within the identified dewatering zone of influence if a decline is recorded during construction dewatering and the decline is a result of dewatering activities. Monitoring may be terminated prior to one year post-construction if initial monitoring determines that there is no evidence of residual effects and levels have returned to pre-construction condition.

Section / Page in REA

#### Table 3-1 Edits to the Initial REA Reports

#### **Combined REA Report and Revision Report text** Report Contingency Measures: appropriate site-specific mitigation has been implemented. discharge towards the feature after applying appropriate water quality and temperature controls. Table 3-4 / page 49 Monitoring Plan and Contingency Measures Monitoring Plan and Contingency Measures • Conduct 3 years post-construction amphibian call surveys (frogs and toads) and egg mass or adult surveys (salamanders) to assess any potential changes in amphibian breeding populations or species distribution (if features determined to be significant) at features potentially affected by construction dewatering (AWO-01, AWO-08, AWO-13, AWO-17, AWO-20 and AMC-01) by a gualified Biologist, using the protocol described above. Biologist, using the protocol described above. Table 3-5 / page 51 Mitigation Strategy Mitigation Strategy Limit dewatering where turbines are constructed within the sand and/or gravel deposits to less than 400,000 L/day. Limit dewatering where turbines are constructed within the sand and/or gravel deposits to less than 400,000 L/day. Table 3-7 / page 58 Mitigation Strategy Mitigation Strategy • Limit dewatering where turbines are constructed within the sand and/or gravel deposits or where shallow water table conditions are expected to be less than 400,000 L/day (Anticipated turbines: 8, 25, and 32-34). <del>32-34)</del>. Avoid dewatering turbines with intersecting radii of influence simultaneously, where possible. areas, existing drainage ditching or agricultural fields. **Contingency Measures Contingency Measures** If surface water levels are temporarily affected from construction dewatering activities, divert water from dewatering activities following appropriate water quality and water temperature controls (i.e. filter bags and/or envirotanks, discharge locations, etc.) to the surface water feature to supplement flow and or surface water levels. **Construction Plan Report** Table 3-3 / page 25 Mitigation Strategy Mitigation Strategy Limit dewatering where turbines are constructed within the sand and/or gravel deposits to less than 400,000 L/day. • Limit dewatering where turbines are constructed within the sand and/or gravel deposits to less than 400,000 L/day. Table 3-3 / page 24-25 Monitoring Plan and Contingency Measures Monitoring Plan and Contingency Measures • For significant natural features within the zone of influence and potentially affected by dewatering activities, the following Monitoring Plan will be implemented: be implemented Prior to construction, undertake monthly monitoring for a minimum of six months of surface water levels (staff gauge), stream flow (if applicable), vertical hydraulic gradients (mini-piezometers), surface water temperature and vegetation health of the feature within the identified dewatering zone of influence. within the identified dewatering zone of influence. During construction dewatering activities, undertake daily monitoring of surface water levels (staff gauge), stream flow (if applicable), vertical hydraulic gradients (mini-piezometers), surface water temperature and vegetation health of the feature within the identified dewatering zone of influence. the identified dewatering zone of influence. · Following construction, undertake monthly monitoring for up to one year of surface water levels (staff gauge), stream flow (if applicable), vertical hydraulic gradients (mini-piezometers), surface water temperature, and vegetation health of the feature within the identified dewatering zone of influence. Monitoring may be terminated prior to one year postconstruction if there is no evidence of residual effects and levels have returned to norms established through pre-construction monitoring. of residual effects and levels have returned to norms established through pre-construction monitoring. dewatering. dewatering. no evidence of residual effects and levels have returned to pre-construction condition. Contingency Measures: Contingency Measures: In the event of a decrease in surface water levels which can be attributed to the dewatering activities, stop dewatering until appropriate site-specific mitigation has been implemented. Implement contingency measures (to be determined in consultation with MNR), if required, including but not limited to rescue of stranded wildlife. MNR), if required, including but not limited to rescue of stranded wildlife.

JER\_05ra\_2014-07-22\_Project\_Modification\_60301207.Docx

#### Revised Text

(Underlined text represents additions and strikethrough text represents deletions.)

In the event of a decrease in surface water levels which can be attributed to the dewatering activities, stop dewatering until

Implement contingency measures, if required, including but not limited to rescue of stranded wildlife and/or directing dewatering

• Conduct 3 years post-construction amphibian call surveys (frogs and toads) and egg mass or adult surveys (salamanders) to assess any potential changes in amphibian breeding populations or species distribution (if features determined to be significant) at features potentially affected by construction dewatering (AWO-01, AWO-03, AWO-05, AWO-08, AWO-13, AWO-17, AWO-20 and AMC-01) by a qualified

• Limit dewatering at all turbines to quantities detailed in Table 4 of the Hydrogeological Report in Support of a Modification to the Renewable Energy Approval for the Jericho Wind Energy Centre, prepared by AECOM in July 2014, where turbines are constructed within the sand and/or gravel deposits or where shallow water table conditions are expected to be less than 400.000 L/day (Anticipated turbines: 8, 25, and

• Set back groundwater discharge locations at least 30 m from significant wetlands. All groundwater discharge will undergo appropriate water quality and temperature controls, as required, and will be directed through a sediment filter (i.e., filter bag), sediment basin or other appropriate device capable of handling the anticipated volumes of water before being discharged to the environment. The specific locations for directing treated groundwater discharge will be selected in the field at the time of construction, but will generally be limited to grassed

If surface water levels are temporarily affected from construction dewatering activities, divert water from dewatering activities following appropriate water quality and water temperature controls (i.e. filter bags and/or envirotanks, discharge locations, etc.) to the surface water feature to supplement flow and or surface water levels. stop dewatering until appropriate site specific mitigation plan has been developed.

• For significant natural features within the zone of influence and potentially affected by dewatering activities, the following Monitoring Plan will

Prior to construction, undertake monthly monitoring for a minimum of six months of surface water levels (staff gauge), stream flow (if applicable), vertical hydraulic gradients (mini-piezometers), surface water temperature and vegetation health of the feature

- During construction dewatering activities, undertake daily monitoring of surface water levels (staff gauge), stream flow (if applicable), vertical hydraulic gradients (mini-piezometers), surface water temperature and vegetation health of the feature within

 Following construction, undertake monthly monitoring for up to one year of surface water levels (staff gauge), stream flow (if applicable), vertical hydraulic gradients (mini-piezometers), surface water temperature, and vegetation health of the feature within the identified dewatering zone of influence. Monitoring may be terminated prior to one year postconstruction if there is no evidence

Prior to construction, conduct site reconnaissance visit and record surface water level (if present) prior to construction.

During Construction, If surface water is present prior to dewatering, monitor surface water levels daily during construction

 Following construction, undertake monthly monitoring for up to one year of surface water levels of the feature within the identified dewatering zone of influence if a decline is recorded during construction dewatering and the decline is a result of dewatering activities. Monitoring may be terminated prior to one year post-construction if initial monitoring determines that there is

In the event of a decrease in surface water levels which can be attributed to the dewatering activities, stop dewatering until appropriate site-specific mitigation has been implemented.-Implement contingency measures (to be determined in consultation with

 Implement contingency measures, if required, including but not limited to rescue of stranded wildlife and/or directing dewatering discharge towards the feature after applying appropriate water quality and temperature controls.

#### Table 3-1 Edits to the Initial REA Reports

Section / Page in REA Report	Combined REA Report and Revision Report text	Revis ( <u>Underlined text</u> represents additions a
Table 3-4 / page 33	<ul> <li>Mitigation Strategy</li> <li>Limit dewatering where turbines are constructed within the sand and/or gravel deposits to less than 400,000 L/day.</li> </ul>	Mitigation Strategy
Table 3-4 / page 32-33	<ul> <li>Monitoring Plan and Contingency Measures</li> <li>For significant natural features within the zone of influence and potentially affected by dewatering activities, the following Monitoring Plan will be implemented: <ul> <li>Prior to construction, undertake monthly monitoring for a minimum of six months of surface water levels (staff gauge), stream flow (if applicable), vertical hydraulic gradients (mini-piezometers), surface water temperature and vegetation health of the feature within the identified dewatering zone of influence.</li> <li>During construction dewatering activities, undertake daily monitoring of surface water levels (staff gauge), stream flow (if applicable), vertical hydraulic gradients (mini-piezometers), surface water temperature and vegetation health of the feature within the identified dewatering zone of influence.</li> <li>Following construction, undertake monthly monitoring for up to one year of surface water levels (staff gauge), stream flow (if applicable), vertical hydraulic gradients (mini-piezometers), surface water temperature, and vegetation health of the feature within the identified dewatering zone of influence.</li> <li>Following construction, undertake monthly monitoring for up to one year of surface water levels (staff gauge), stream flow (if applicable), vertical hydraulic gradients (mini-piezometers), surface water temperature, and vegetation health of the feature within the identified dewatering zone of influence. Monitoring may be terminated prior to one year postconstruction if there is no evidence of residual effects and levels have returned to norms established through pre-construction monitoring.</li> </ul> </li> <li>Contingency Measures: <ul> <li>In the event of a decrease in surface water levels which can be attributed to the dewatering activities, stop dewatering until appropriate site-specific mitigation has been implemented. Implement contingency measures (to be determined in consultation with MNR), if required, including but not limited to rescue of strand</li></ul></li></ul>	<ul> <li>Monitoring Plan and Contingency Measures</li> <li>For significant natural features Turtle Wintering Habitat within the zero following Monitoring Plan will be implemented: <ul> <li>Prior to construction, undertake monthly monitoring for a flow (if applicable), vertical hydraulic gradients (mini-piezor within the identified dewatering zone of influence.</li> <li>During construction dewatering activities, undertake dai applicable), vertical hydraulic gradients (mini-piezometers), the identified dewatering zone of influence.</li> <li>Following construction, undertake monthly monitoring for applicable), vertical hydraulic gradients (mini-piezometers), the identified dewatering zone of influence.</li> <li>Following construction, undertake monthly monitoring for applicable), vertical hydraulic gradients (mini-piezometers), the identified dewatering zone of influence. Monitoring may of residual effects and levels have returned to norms estabe</li> </ul> </li> <li>Contingency Measures: <ul> <li>In the event of a decrease in surface water levels which appropriate site-specific mitigation has been implemented. MNR), if required, including but not limited to rescue of strates activities, the following Monitoring Plan will be implemented:</li> <li>Prior to construction, conduct site reconnaissance visit ar During Construction, undertake monthly monitoring for identified dewatering zone of influence if a decline is record dewatering activities. Monitoring may be terminated prior to no evidence of residual effects and levels have returned to</li> </ul> </li> <li>Contingency Measures: <ul> <li>In the event of a decrease in surface water levels which appropriate site-specific mitigation has been implemented.</li> <li>MNR), if required, including may be terminated prior to dew following construction, undertake monthly monitoring for identified dewatering zone of influence if a decline is record dewatering activities. Monitoring may be terminated prior to no evidence of residual effects and levels have returned to no evi</li></ul></li></ul>
Table 3-5 / page 41	Mitigation Strategy	discharge towards the feature after applying appropriate was Mitigation Strategy
Section 3.3.2 / page 49	<ul> <li>Limit dewatering where turbines are constructed within the sand and/or gravel deposits to less than 400,000 L/day.</li> <li>The extraction of groundwater for construction dewatering purposes is expected to be of low volume due to the short duration of dewatering activities, and the shallow depth of the turbine bases and collection lines (up to 4 mbgs and 2 mbgs respectively). However, there is the potential that water taking could be greater than 50,000 L/day, depending on the surficial material being excavated, the depth to groundwater, the amount of precipitation received during excavation activities, and other geological characteristics that were observed during the geotechnical investigation. The following turbines have been determined, through the analysis of the geotechnical study prepared by AMEC (2013), available geological mapping and MOE water well record borehole logs, to have the potential to require construction dewatering of greater than 50,000 L/day during the excavation and installation of turbine foundations: 8, 25, and 32-34. The location and extent of construction dewatering associated with collection line installation varies depending on sufficial geological material encountered, the depth to groundwater as indicated in MOE water well records and the presence of groundwater indicators observed during field investigations. All dewatering activities associated with turbine foundations and collection lines are anticipated to be less than 400,000 L/day.</li> <li>As such the water taking may be classified as Groundwater – Category 2 (short-term, non-recurring taking less than 30 consecutive days and less than 400,000 L/day to 214,400 L/day with calculated radii of influence for the construction dewatering associated with turbine foundations. Based on the calculations in Appendix B-1, the conservative water taking per turbine base excavation range from 95,860 L/day to 214,400 L/day with calculated radii of influence for the construction dewatering associated with collection li</li></ul>	• Limit dewatering where turbines are constructed within the sand and The extraction of groundwater for construction dewatering purposes is a activities, and the shallow depth of the turbine bases and collection line that for water taking could be greater than 50,000 above 400,000 L/day depth to groundwater, the amount of precipitation received during excar during the geotechnical investigation. The following turbines have been AMEC (2013), available geological mapping and MOE water well record greater than 50,000 L/day during the excavation and installation of turbi study prepared by AMEC (2013), available geological mapping, MOE w excavation, Jericho has determined that all turbines proposed for the Pr potential to require construction dewatering greater than 400,000 L/day and extent of construction dewatering greater than 400,000 L/day and extent of construction dewatering associated with collection line ins depth to groundwater as indicated in MOE water well records and the p dewatering activities associated with turbine foundations and collection As such the water taking for turbine foundations may be classified as 30 consecutive days and less than 400,000 L/day taking greater than amount of water needed for safe construction practices. Appendix B- <i>Renewable Energy Approval for the Jericho Wind Energy Centre</i> (Hyd detailed calculations on the dewatering estimates and radii of influend Based on the calculations in Appendix B-1 the report, the conservativ <del>95,860</del> 50,000 L/day to 214,400 1,244,506 L/day with calculated radii <u>65.97</u> m and 278 214.88 m. Appendix B-2 contains detailed calculatio construction dewatering associated with collection line installation. B for collection lines installed in permeable surficial material is approxin As these calculations are based on estimations from the available dat location and these calculations will be revisited using the new soil dat

#### vised Text

s and strikethrough text represents deletions.)

#### and/or gravel deposits to less than 400,000 L/day.

zone of influence and potentially affected by dewatering activities, the

or a minimum of six months of surface water levels (staff gauge), stream zometers), surface water temperature and vegetation health of the feature

daily monitoring of surface water levels (staff gauge), stream flow (if s), surface water temperature and vegetation health of the feature within

g for up to one year of surface water levels (staff gauge), stream flow (if rs), surface water temperature, and vegetation health of the feature within hay be terminated prior to one year postconstruction if there is no evidence ablished through pre-construction monitoring.

ich can be attributed to the dewatering activities, stop dewatering until d. Implement contingency measures (to be determined in consultation with tranded wildlife.

bitat within the zone of influence and potentially affected by dewatering

and record surface water level (if present) prior to construction dewatering. dewatering, monitor surface water levels daily during construction dewatering. g for up to one year of surface water levels of the feature within the orded during construction dewatering and the decline is a result of r to one year post-construction if initial monitoring determines that there is to pre-construction condition.

ch can be attributed to the dewatering activities, stop dewatering until d.

ng but not limited to rescue of stranded wildlife and/or directing dewatering water quality and temperature controls.

and/or gravel deposits to less than 400,000 L/day.

is expected to be of low volume due to the short duration of dewatering nes (up to 4 mbgs and 2 mbgs respectively). However, there is the potential <u>lay to be required</u>, depending on the surficial material being excavated, the cavation activities, and other geological characteristics that were observed en determined, through the analysis of the geotechnical study prepared by cord borehole logs, to have the potential to require construction dewatering of white foundations: 8, 25, and 32-34. Based the analysis of the geotechnical <u>E water well record borehole logs</u>, and potential precipitation during <u>Project</u>, excluding turbines that have already been constructed, have the lay during the excavation and installation of turbine foundations. The location installation varies depending on surficial geological material encountered, the e presence of groundwater indicators observed during field investigations. All on lines are anticipated to be less than 400,000 L/day.

as Groundwater – Category 2 <u>3</u> (<del>short term, non recurring taking less than</del> an 400,000 L/day). <u>In all cases, Jericho will only remove the minimum</u> <u>B-1</u> The *Hydrogeological Report in Support of a Modification to the* <u>Hydrogeological Report</u>), prepared by AECOM in July 2014 contains ence for the construction dewatering associated with turbine foundations. ative water taking of <u>groundwater</u> per turbine base excavation range from adii of influence for the construction dewatering <del>of</del> ranging between <del>131</del> ations of the dewatering estimates and radius of influence for the Based on the calculations in Appendix B-2, the conservative water taking ximately 174,300 L/day with a calculated radius of influence of 77 m.

data, at least one geotechnical borehole will be drilled for each turbine base data and depth to groundwater found from the geotechnical investigations.

#### Table 3-1 Edits to the Initial REA Reports

Section / Page in REA Report	Combined REA Report and Revision Report text	Revis ( <u>Underlined text</u> represents additions a
Table 3-6 / page 49	Mitigation Strategy • Limit dewatering where turbines are constructed within the sand and/or gravel deposits or where shallow water table conditions are expected to be less than 400,000 L/day (Anticipated turbines: 8, 25, and 32-34).	Mitigation Strategy • Limit dewatering <u>at all turbines to quantities detailed in Table 4 of the</u> <i>Energy Approval for the Jericho Wind Energy Centre</i> , prepared by AE and/or gravel deposits or where shallow water table conditions are ex <del>32-34)</del> .
		Avoid dewatering turbines with intersecting radii of influence simulta     Set back groundwater discharge locations at least 30 m from signific     guality and temperature controls, as required, and will be directed threappropriate device capable of handling the anticipated volumes of wa     for directing treated groundwater discharge will be selected in the field     areas, existing drainage ditching or agricultural fields.
	<b>Contingency Measures</b> If surface water levels are temporarily affected from construction dewatering activities, divert water from dewatering activities following appropriate water quality and water temperature controls (i.e. filter bags and/or envirotanks, discharge locations, etc.) to the surface water feature to supplement flow and or surface water levels.	Contingency Measures If surface water levels are temporarily affected from construction dew appropriate water quality and water temperature controls (i.e. filter ba feature to supplement flow and or surface water levels. stop dewatering
Design and Operations	Report	
Table 6-2 / page 28	<ul> <li>Monitoring Plan and Contingency Measures</li> <li>Conduct 3 years post-construction amphibian call surveys (frogs and toads) and egg mass or adult surveys (salamanders) to assess any potential changes in amphibian breeding populations or species distribution (if features determined to be significant) at features potentially affected by construction dewatering (AWO-01, AWO-08, AWO-13, AWO-17, AWO-20 and AMC-01) by a qualified Biologist, using the protocol described above.</li> </ul>	<ul> <li>Monitoring Plan and Contingency Measures</li> <li>Conduct 3 years post-construction amphibian call surveys (frogs an potential changes in amphibian breeding populations or species dis affected by construction dewatering (AWO-01, <u>AWO-03, AWO-05, AB</u>iologist, using the protocol described above.</li> </ul>
Water Assessment and	Water Body Report	
Section 5.3 / page 250	<ul> <li>Dewatering Activities (if necessary)</li> <li>Limit dewatering where turbines are constructed within the sand and/or gravel deposits to less than 400,000 L/day.</li> </ul>	Dewatering Activities (if necessary) • Limit dewatering where turbines are constructed within the sand and
Table 5-8 / page 263	<ul> <li>Mitigation Strategy (Refer to Section 5.3 for Mitigation Measures)</li> <li>Limit dewatering where turbines are constructed within the sand and/or gravel deposits to less than 400,000 L/day.</li> </ul>	Limit dewatering where turbines are constructed within the sand and
Decommissioning Plan	Report	
There are no edits to the De	commissioning Plan Report resulting from the modifications described in Section 2.	
Wind Turbine Specifica	ition Report	
There are no edits to the Wi	nd Turbine Specification Report resulting from the modifications described in Section 2.	

### vised Text

and strikethrough text represents deletions.)

f the Hydrogeological Report in Support of a Modification to the Renewable AECOM in July 2014, where turbines are constructed within the sand expected to be less than 400,000 L/day (Anticipated turbines: 8, 25, and

ultaneously, where possible.

hificant wetlands. All groundwater discharge will undergo appropriate water through a sediment filter (i.e., filter bag), sediment basin or other water, before being discharged to the environment. The specific locations field at the time of construction, but will generally be limited to grassed

ewatering activities, <del>divert water from dewatering activities following bags and/or envirotanks, discharge locations, etc.) to the surface water ering until appropriate site specific mitigation plan has been developed.</del>

and toads) and egg mass or adult surveys (salamanders) to assess any distribution (if features determined to be significant) at features potentially <u>5</u>, AWO-08, AWO-13, AWO-17, AWO-20 and AMC-01) by a qualified

and/or gravel deposits to less than 400,000 L/day.

and/or gravel deposits to less than 400,000 L/day.



# 4. Summary and Conclusions

The Project modification described in this REA Project Modification Report do not change the overall conclusion of the Project Description Report (February, 2013) and associated Revision to the Project Description Report (October, 2013) which state that "this project can be constructed, installed and operated without any significant adverse residual effects to the environment. Post-construction monitoring related to effects on wildlife, including birds and bats, will be undertaken to confirm this conclusion".



# **Appendix A**

Hydrogeological Report in Support of a Modification to the Renewable Energy Approval for the Jericho Wind Energy Centre



Jericho Wind, Inc.

Hydrogeological Report in Support of a Modification to the Renewable Energy Approval for the Jericho Wind Energy Centre



Environment

tel

fax



Jericho Wind, LP.

## Hydrogeological Report in Support of a Modification to the Renewable Energy Approval for the Jericho Wind Energy Centre

Prepared by:	
AECOM	
105 Commerce Valley Drive West, Floor 7	905 886 7022
Markham, ON, Canada L3T 7W3	905 886 9494
www.aecom.com	

Project Number: 60301207

Date: July, 2014



# **Statement of Qualifications and Limitations**

The attached Report (the "Report") has been prepared by AECOM Canada Ltd. ("Consultant") for the benefit of the client ("Client") in accordance with the agreement between Consultant and Client, including the scope of work detailed therein (the "Agreement").

The information, data, recommendations and conclusions contained in the Report (collectively, the "Information"):

- is subject to the scope, schedule, and other constraints and limitations in the Agreement and the qualifications contained in the Report (the "Limitations");
- represents Consultant's professional judgement in light of the Limitations and industry standards for the preparation of similar reports;
- may be based on information provided to Consultant which has not been independently verified;
- has not been updated since the date of issuance of the Report and its accuracy is limited to the time period and circumstances in which it was collected, processed, made or issued;
- must be read as a whole and sections thereof should not be read out of such context;
- was prepared for the specific purposes described in the Report and the Agreement; and
- in the case of subsurface, environmental or geotechnical conditions, may be based on limited testing and on the assumption that such conditions are uniform and not variable either geographically or over time.

Consultant shall be entitled to rely upon the accuracy and completeness of information that was provided to it and has no obligation to update such information. Consultant accepts no responsibility for any events or circumstances that may have occurred since the date on which the Report was prepared and, in the case of subsurface, environmental or geotechnical conditions, is not responsible for any variability in such conditions, geographically or over time.

Consultant agrees that the Report represents its professional judgement as described above and that the Information has been prepared for the specific purpose and use described in the Report and the Agreement, but Consultant makes no other representations, or any guarantees or warranties whatsoever, whether express or implied, with respect to the Report, the Information or any part thereof.

Without in any way limiting the generality of the foregoing, any estimates or opinions regarding probable construction costs or construction schedule provided by Consultant represent Consultant's professional judgement in light of its experience and the knowledge and information available to it at the time of preparation. Since Consultant has no control over market or economic conditions, prices for construction labour, equipment or materials or bidding procedures, Consultant, its directors, officers and employees are not able to, nor do they, make any representations, warranties or guarantees whatsoever, whether express or implied, with respect to such estimates or opinions, or their variance from actual construction costs or schedules, and accept no responsibility for any loss or damage arising therefrom or in any way related thereto. Persons relying on such estimates or opinions do so at their own risk.

Except (1) as agreed to in writing by Consultant and Client; (2) as required by-law; or (3) to the extent used by governmental reviewing agencies for the purpose of obtaining permits or approvals, the Report and the Information may be used and relied upon only by Client.

Consultant accepts no responsibility, and denies any liability whatsoever, to parties other than Client who may obtain access to the Report or the Information for any injury, loss or damage suffered by such parties arising from their use of, reliance upon, or decisions or actions based on the Report or any of the Information ("improper use of the Report"), except to the extent those parties have obtained the prior written consent of Consultant to use and rely upon the Report and the Information. Any injury, loss or damages arising from improper use of the Report shall be borne by the party making such use.

This Statement of Qualifications and Limitations is attached to and forms part of the Report and any use of the Report is subject to the terms hereof.



AECOM 105 Commerce Valley Drive West, Floor 7 Markham, ON, Canada L3T 7W3 www.aecom.com

905 886 7022 tel 905 886 9494 fax

July 22, 2014

Mr. Ben Greenhouse NextEra Energy Resource, LLC 700 Universe Blvd. Juno Beach, FL 33408

Dear Mr. Greenhouse:

Project No: 60301207

### Regarding: Hydrogeological Report in Support of a Modification to the Renewable Energy Approval for the Jericho Wind Energy Centre

The purpose of this letter is to provide additional hydrogeological information and discussion in support of a modification to Condition H1 and H2 of the REA approval for the Jericho Wind Energy Centre for construction related dewatering activities associated with turbine foundation construction.

On behalf of Jericho Wind, LP., AECOM is pleased to submit the following Hydrogeological Assessment. The attached report provides background information on the proposed undertaking, the physical setting of the site, subsurface hydrogeological conditions, an assessment of potential impacts of construction dewatering and discharge of water to the environment, and a monitoring plan and mitigation measures to address potential impacts.

Should you or any technical reviewer have any questions regarding this submission, please contact the undersigned at 905-747-7793 or Marie Wardman at 905-747-7598.

Sincerely, AECOM Canada Ltd.

Mar Pore

Marc Rose, MES, MCIP, RPP Senior Environmental Planner Marc.Rose@aecom.com

MR:mm Attach



# **Distribution List**

# of Hard Copies	PDF Required	Association / Company Name
	YES	Jericho Wind, LP
	YES	AECOM Canada Ltd.
3		Ministry of the Environment

AD PROFESSIONAL FLA

<del>100049</del>220

71221201

ROUNCE OF ONTAHIO

## **AECOM Signatures**

**Report Prepared By:** 

Erin Wilson, B.Sc (Hons) **Environmental Scientist** 

Sam\_

**Caroline Boros** Aquatic Ecologist, Environment

Ward

Jessica MacKay Ward, Ph.D. Ecologist

**Report Reviewed By:** 

Marie Wardman, P.Eng. Senior Geological Engineer

M. Wardma

deman

Jillian deMan, H.B.Sc. Terrestrial & Wetland Ecologist, Environment

Gary Epp, B.Sc.(Hons.), M.Sc., Ph.D. Director of Ecology, Water & Natural Resources, Environment